

RESOLUTION 2020 - 04

**A RESOLUTION OF THE CITY COUNCIL OF THE
CITY OF SUNNYSIDE, WASHINGTON, AUTHORIZING AN
AGREEMENT WITH VAN BELLE EXCAVATING, LLC
TO EXTEND A WATER AND SEWER INTO THILL AVENUE**

WHEREAS, the City is responsible to operate and maintain all water system infrastructure within the City limits; and

WHEREAS, staff has identified the need to extend an 8" water and sewer main approximately 150' to the west to serve the lots on Thill Avenue; and

WHEREAS, the cost to extend the water and sewer main is \$54,475.00, which includes all materials and installation; and

WHEREAS, the City of Sunnyside City Council finds and determines that the extension of this infrastructure is in the best interest of the residents of the City of Sunnyside and will promote the general health, safety and welfare;

NOW, THEREFORE, IT IS HEREBY RESOLVED BY THE CITY COUNCIL OF THE CITY OF SUNNYSIDE, WAHSINGTON, as follows:

SECTION 1. The City Council of the City of Sunnyside authorizes the extension of 150' of 8" water and sewer main into Thill Avenue by Van Belle Excavating, LLC, in accordance with the quotation which is attached hereto as Exhibit "A" and incorporated herein by this reference; and the City Manager is hereby authorized to execute and administer an agreement for and on behalf of the City of Sunnyside.


SECTION 2. This Resolution shall be effective upon passage, approval and signatures hereon in accordance with law.

PASSED this 10th day of February, 2020.



FRANCISCO GUERRERO, MAYOR

ATTEST:

A handwritten signature in black ink, appearing to read "Jacqueline Renteria". The signature is written in a cursive style with a large initial "J" and "R".

JACQUELINE RENTERIA, CITY CLERK

EXHIBIT A

Van Belle Excavating, LLC
P.O. Box 751
Prosser, WA 99350 US
509-781-0551
kyle@vbexcavating.com
www.vbexcavating.com

Estimate



ADDRESS
City of Sunnyside.
818 E Edison Ave
Sunnyside, WA 98944

ESTIMATE #	DATE	EXPIRATION DATE
2263	01/16/2020	02/16/2020

ACTIVITY	AMOUNT
Supply materials and install 150' of 8" water main west of Rossier rd. including the following :	36,925.00T

- Saw cut and remove asphalt, gutter and sidewalk.
- Remove 6" tee and install 8" cross with 4 vales, one on each side.
- Cap the north side of cross with MJ cap and concrete thrust block.
- 2 - 8"x6" reducers, one on the east side of the cross and one on the south side of cross. Connect to existing 6" ac pipe.
- 150' of 8" CR18 C-900 PVC pipe on west side of cross.
- 1 - 8x6" tee with gate valve and thrust block.
- 18' of 6" D.I. pipe, 4.5' bury hydrant and thrust block.
- 3 - 1" water services. All three services will be in the same location and within 50' of the mainline.
- Export dirt and import top course gravel for all trench backfill.
- Pour back gutter, sidewalk and patch asphalt
- Restore gravel road.
- Equipment mobilization and prevailing wage rates.

Supply materials and install 150' of 8" sewer west of Rossier rd. including the following :	17,550.00T
---	------------

- Saw cut and remove asphalt, gutter and sidewalk.
- Core drill and tie 8" sewer pipe into existing manhole.
- Install 150' of 8" sewer with three 4" side services and a 8" clean out at the end of the run.
- Export dirt and import top course gravel for all trench backfill.
- Pour back gutter, sidewalk and patch asphalt.
- Restore gravel road.
- Equipment mobilization and prevailing wage rates.

Not included in bid :

- Rock, hard pan, ground water, boulders or any other solid or unstable soil. Buried asphalt, concrete, tanks, structures or any other foreign objects buried in the ground.
- Breaking rock or dewatering.
- Unmarked private utilities. Locates will be called in and any private unmarked utilities will need to be located by others.
- Relocate or reroute existing utilities.